

Custom Control Panel

Function:

The **Custom Control Panel** is designed and manufactured on an individual project basis. Each U.L. Listed panel is delivered pre-wired, pre-assembled and tested. All panels include three-position main operation cam switches, pilot lights indicating the operational status of the fountain, combination motor starter for the fountain pumps, and contractors and overload relays rated to match the fountain pump size.

If the fountain is equipped with lighting, the panel will include lighting circuits rated at 115/230 volt AC single phase with door mounted pilot lights indicating the status of the fountain's lighting system.

The water level control monitor is integrated into the custom control panel on projects utilizing the 484 Series or 486 Series Water Level Sensors.

For fountains which have a wind compensation system, the wind compensation panel is mounted on the door of the panel for easy access.

Please contact our office for assistance in designing a Custom Control Panel which meets your fountain project requirements.



Key Features:

- Custom built for your application.
- Delivered pre-wired, pre-assembled, and pre-tested.
- Panels are U.L. Listed.